

Declaration of Performance



AJS Window Installations Ltd.
Bridge Trading Estate
Smethwick
B66 2BZ

16

DoP No: 4- 20/11/2015

Liniar Un-glazed top hung Casement Window
Intended for use in domestic or commercial refurbishment or new building applications.

Annex ZA.1 of BS EN 14351-1:2006+A1:2010

Water tightness: No Performance Determined

Dangerous substances: None released under normal indoor use.

Resistance to wind load: No Performance Determined

Load-bearing capacity of safety devices: Pass, 350N when fitted (1 & 2)

Acoustic performance: No Performance Determined

Thermal transmittance: No Performance Determined

Radiation Properties: No Performance Determined

Air permeability: No Performance Determined

A Factory Production Control (FPC) system is established, documented and maintained in accordance with AVCP System 3 as per Annex ZA.2 of BS EN 14351-1:2006+A1:2010.

- (1) Report No. W13001-2 dated 05/02/2013 for Safety & Security friction hinges with built in restrictor - Notified Test Body: Build Check No. 4044**
- (2) Report No. W13001-20 dated 05/02/2013 for Safety & Security friction hinges with built in restrictor - Notified Test Body: Build Check No. 4044**

Scott O'Sullivan
Director

AJS Window Installations Ltd
20 November 2015